

Lawrence Berkeley National Laboratory

Lawrence Berkeley National Laboratory

Title

Survey of the ATLAS Pixel Detector Components

Permalink

<https://escholarship.org/uc/item/7tb4s9w0>

Authors

Andreazza, A.
ATLAS

Publication Date

2009-01-07

Survey of the ATLAS Pixel Detector Components

**Attilio Andreazza, Vadim Kostyukhim,
Ronald Madaras**

This work was supported by the Director, Office of Science, Office of Basic Energy Sciences, of the U.S. Department of Energy under Contract No. DE-AC02-05CH11231.

DISCLAIMER

This document was prepared as an account of work sponsored by the United States Government. While this document is believed to contain correct information, neither the United States Government nor any agency thereof, nor The Regents of the University of California, nor any of their employees, makes any warranty, express or implied, or assumes any legal responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by its trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof, or The Regents of the University of California. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof or The Regents of the University of California.

ATLAS NOTE

March 19, 2008

Survey of the ATLAS Pixel Detector Components

Attilio Andreazza

I.N.F.N. and Dipartimento di Fisica, Milano, Italy

Vadim Kostyukhin

I.N.F.N. Genova, Italy

Ronald J. Madaras

Lawrence Berkeley National Laboratory, Berkeley, CA, USA

Abstract

This document provides a description of the survey performed on different components of the ATLAS Pixel Detector at different stages of its assembly.



Table of Contents

1	INTRODUCTION	3
2	SURVEY PROCEDURES.....	4
2.1	Stave Survey	4
2.1.1	Reference system definition	4
2.1.2	R Φ survey	4
2.1.3	RZ survey.....	4
2.1.4	Average plane and distortions	4
2.2	Halfshell Survey	7
2.2.1	Reference system definition	7
2.2.2	Stave measurement.....	7
2.3	Sector and Disk Surveys	10
2.3.1	Goal of the Survey	10
2.3.2	Module Alignment Parameters.....	10
2.3.3	Description of the Sector and Disk Surveys.....	12
2.3.4	Calculation of the Survey Module Alignment Parameters	13
3	STORAGE OF SURVEY DATA	14
3.1	RDB Data Structure	14
3.2	PDB Test Definition.....	14
3.2.1	Sphere Coordinates	14
3.2.2	Stave survey.....	15
3.2.3	Halfshell survey.....	17
3.3	Data from Sector and Disk Surveys.....	19
4	SUMMARY OF RESULTS.....	20
4.1	Results for Barrel Modules	20
4.1.1	Comparison between stave and halfshell survey.....	20
4.1.2	Module distortions	21
4.1.3	Comparison to ideal halfshell geometry	22
4.2	Results for Disk Modules.....	23
4.2.1	Results of the X,Y and Z sector surveys.....	23
4.2.2	Results of the X,Y disk surveys	25
4.2.3	Measurement Precision and Stability.....	26
4.2.4	Additional Uncertainty for Back Module Alignment Parameters.....	27
4.2.5	Conclusion for Disk Modules.....	28

1 Introduction

During the production of the ATLAS pixel detector great care was put in the geometrical survey of the location of the sensitive area of modules. This had a double purpose:

- to provide a check of the quality of the assembly procedure and assure tolerances in the geometrical assembly were met;
- to provide an initial point for the alignment (the so called “as-built detector”), better than the ideal geometry.

Since direct access to the sensitive area becomes more and more difficult with the progress of the assembly, the survey needed to be performed at different stages: after module loading on the local supports (sectors and staves) and after assembly of the local supports in disks or halfshells.

Different techniques were used, including both optical 2D and 3D surveys and mechanical survey.

This document summarizes the survey procedures, the analysis done on the collected data and how survey data are stored in case they will need to be accessed in the future.




Figure 1: Stave drawing and survey reference system.

2 Survey Procedures

2.1 Stave Survey

2.1.1 Reference system definition

A barrel stave layout and its reference system are shown in Figure 1. The y-axis is defined by the normal to the reference planes at the edge of the stave, the z-axis is given by the direction of one well machined edge of the stave.

This machined edge is not accessible after the modules have been mounted on the stave, therefore the stave reference frame is determined by a mechanical survey of the local support along with a touching probe. In this reference system, the positions of the ruby balls at the edge of the stave are also measured.

When the staves are loaded [1], the X-Z positions of the ruby balls are measured using an optical probe. These are used to set the stave reference system for the survey.

2.1.2 RΦ survey

In the X-Z plane the full stave is measured optically in 2D.

The targets are four reference marks on the sensor surface, which are visible through openings in the flex hybrids [2]. They can be directly connected to the sensitive area, being at coordinates $x=\pm 8.9$ mm, $z=\pm 29.9$ mm, from the centre of the active area.

For redundancy, in case the above mentioned alignment marks are not visible, corners of the front-end chips are also measured. Their position with respect to the sensitive area is less known due to uncertainty in the flip-chip process, but in any case at the level of few micrometers.

The alignment marks are used to determine the x and z coordinates of the sensitive area region centre and the rotation of the module about the y-axis.

2.1.3 RZ survey

The optical probe used for the loaded stave reference system determination and the RΦ survey does not have enough resolution to provide an acceptable precision on the vertical (y) coordinate.

This is performed using different techniques in the different stave assembly sites, to access some specific points on the front-end surface.

The two lines of points, which are collected at $x=\pm 11$ mm are then fitted to a circle given by the following equation, where the parameters are indicated in Figure 2 and θ is the angle of the tangent to the circle at the nominal center of module z_c , defined to be negative if oriented like in the figure 2:

$$(z - z_c + R \sin \theta)^2 + (y - Y_c - R \cos \theta)^2 = R^2$$

for which a parabolic approximation can also be given:

$$y = Y_c + (z - z_c) \tan \theta + \frac{1}{2} \frac{(z - z_c)^2}{R \cos \theta}$$

2.1.4 Average plane and distortions

Putting together all the parameters, survey data for each module consist therefore of the following nine quantities:

- x_c, z_c, ε_y : position of the center of the active area and orientation of the modules in the x-z plane, given from 2D survey
- y_{c+}, R_+, θ_+ , parameter of the circle describing the edge of the module at $x=+11$ mm
- y_{c-}, R_-, θ_- , parameter of the circle describing the edge of the module at $x=-11$ mm

Interpolating between the two module edges, the module surface can be described with a sub-micrometer accuracy, by the following equation:

$$y = \frac{(x - x_c) + 11 \text{ mm}}{22 \text{ mm}} \left[Y_{c+} + (z - z_c) \tan \theta_+ + \frac{1}{2} \frac{(z - z_c)^2}{R_+ \cos \theta_+} \right] + \frac{11 \text{ mm} - (x - x_c)}{22 \text{ mm}} \left[Y_{c-} + (z - z_c) \tan \theta_- + \frac{1}{2} \frac{(z - z_c)^2}{R_- \cos \theta_-} \right]$$

which can be decomposed in a linear term, describing a plane and two distortion terms:

$$\begin{aligned} y = & \frac{Y_{c+} + Y_{c-}}{2} + (x - x_c) \frac{Y_{c+} - Y_{c-}}{22 \text{ mm}} + (z - z_c) \frac{\tan \theta_+ + \tan \theta_-}{2} \\ & + (x - x_c)(z - z_c) \frac{\tan \theta_+ - \tan \theta_-}{22 \text{ mm}} \\ & + \frac{1}{2} (z - z_c)^2 \left[\frac{1}{2} \left(\frac{1}{R_+ \cos \theta_+} + \frac{1}{R_- \cos \theta_-} \right) + \frac{x - x_c}{22 \text{ mm}} \left(\frac{1}{R_+ \cos \theta_+} - \frac{1}{R_- \cos \theta_-} \right) \right] \end{aligned}$$

If we now define the quantities:

$$\begin{aligned} y_c &= \frac{Y_{c+} + Y_{c-}}{2} \\ \tan \varepsilon_z &= \frac{Y_{c+} - Y_{c-}}{22 \text{ mm}} \\ \tan \varepsilon_x &= \frac{\tan \theta_+ + \tan \theta_-}{2} \\ \theta &= \theta_+ - \theta_- \\ \kappa_{\pm} &= \frac{1}{R_{\pm}} \end{aligned}$$

and neglect the very small difference between $\cos \theta_+$ and $\cos \theta_-$, we can summarize the above result saying that the transformation that brings the local coordinates (in the module plane) to the stove frame is given by:

$$\begin{pmatrix} x \\ y \\ z \end{pmatrix} = \begin{pmatrix} \cos \varepsilon_y & \approx 0 & \sin \varepsilon_y \\ \sin \varepsilon_z & \approx 1 & \sin \varepsilon_x \\ -\sin \varepsilon_y & \approx 0 & \cos \varepsilon_y \end{pmatrix} \begin{pmatrix} x_{\text{local}} \\ 0 \\ z_{\text{local}} \end{pmatrix} + \begin{pmatrix} x_c \\ y_c \\ z_c \end{pmatrix}$$

with the additional out of plane correction:

$$y_{\text{local}} = \frac{x_{\text{local}} z_{\text{local}} \theta}{22 \text{ mm}} + \frac{1}{2} z_{\text{local}}^2 \left(\frac{\kappa_+ + \kappa_-}{2} + \frac{x_{\text{local}} (\kappa_+ - \kappa_-)}{22 \text{ mm}} \right)$$

These parameters (coordinates of the module center, three angles and distortions) are stored in the production database as described in Section 3.




Figure 2: Points measured along the edge of a module: the fitting program provides the curvature radius and the tangent to the circle at the nominal centre of the module, separately for the two sides.

2.2 Halfshell Survey

2.2.1 Reference system definition

The halfshell survey is performed in the ATLAS frame.

The link between the ATLAS frame and the CMM frame is done by measuring ruby balls located on the halfring used as support points for the staves. These ruby balls have been inspected at Peine (D), after the assembly of the empty halfshells, and results are reported in the figures attached to this document (see Section 5).

Six of these ruby balls are accessible for layer 1 and 2 halfshells, only four for the B-Layer. The transformation is computed by the CMM software using three selected ruby balls and matching the CMM reference frame with the ATLAS coordinates determined at Peine.

Changing the selection of the ruby balls results in reference systems which differ at most by 200 μm within the sensitive region of the pixel detector.

2.2.2 Stave measurement

For each stave are measured:

- the position of the ruby ball on the C-side,
- six points on the carbon-carbon plane below the ruby ball on the C-side,
- the position of the ruby ball on the A-side,
- six points on the carbon-carbon plane below the ruby ball on the A-side.

The six points on each side are fitted together to provide the equation of the carbon-carbon plane. Notice that the points are not compensated for the size of the touching probe, since this correction needs to know the orientation of the plane. Therefore after the fit the plane must be translated inwards by a distance equal to the radius of the touching probes (0.496 mm in our setup).

In the same way all the twelve points (six on A-side and six on C-side) are fitted together to provide an average stave plane. This plane is the corresponding one to the $y=0$ plane in the stave survey. A measurement is accepted if:

- deviation from sphericity of a ruby ball is less than 10 μm (fabrication tolerance $\pm 0.125 \mu\text{m}$ [3]);
- difference from nominal diameter of a ruby ball is less than 20 μm (fabrication tolerance $\pm 1 \mu\text{m}$ [3]);
- deviation from planarity of one of the end-planes is bigger than 50 μm (fabrication tolerance $\pm 10 \mu\text{m}$ [4]).

These cuts take into account the different quality of the ruby ball and carbon-carbon surfaces, and the strong correlation between the fitted diameter and the position of the centre of the sphere: given the few (5) measured points on each ball and their distribution, it may happen that the deviation from sphericity is small, while the centre is badly computed. The check on the diameter allows one to detect such problems.

Staves are measured always in a clockwise order as seen from the C-side (Figure 3) [5].

Labels to understand the geometrical objects in the report files available in the RDB, are indicated in Table 1.

Every halfshell is measured twice and the differences between the two set of measurements are computed in order to detect outliers and, if needed, repeat the measurements on them. The r.m.s. of these differences are quoted in Table 2. At the end the two measurements are averaged to provide the best estimation for the parameters. The uncertainty in these averages should be half the size of the r.m.s. of the differences.




Figure 3: Stave numbering and split planes between top and bottom halfshells, from [5]. During halfshell survey, staves are measured in clockwise order, according to this picture.

Table 1: Identifiers of the survey objects in the raw data file. The ## character pairs indicates the progressive stave number within the halfshell.

Label	Description
SP##1	C-side ruby ball
PT##2-PT##7	Not-compensated points on the carbon-carbon plane below the C-side ruby ball
PL##8	Plane fitted through PT##2-PT##7
PL##9	PL##8 corrected for the size of touching probe
PT##10	Projection of di SP##1 on PL##9
SA##1	A-side ruby ball
PTA##2-PTA##7	Not-compensated points on the carbon-carbon plane below the A-side ruby ball
PA##8	Plane fitted through PTA##2-PTA##7
PA##9	PA##8 corrected for the size of touching probe
PL3##	Plane fitted through the 12 points PT##2-PT##7 e PTA##-PTA##7
PL4##	PL3## corrected for the size of touching probe

Table 2: The r.m.s. of differences between two half shell measurements

Halfshell	Ruby balls			Average planes		
	R [μm]	R Φ [μm]	Z [μm]	R-Z tilt [$^\circ$]	R Φ tilt [$^\circ$]	R [μm]
B-layer bottom	5.7	3.4	3.9	0.0007	0.036	6.0
B-layer top	7.3	3.8	3.5	0.0007	0.021	7.7
Layer-1 bottom	8.5	6.3	3.5	0.0005	0.024	7.0
Layer-1 top	12.2	21.9	3.8	0.0009	0.045	2.6
Layer-2 bottom	15.6	14.8	7.9	0.0019	0.024	8.7
Layer-2 top	6.0	4.5	3.6	0.0008	0.025	2.8

2.3 Sector and Disk Surveys

2.3.1 Goal of the Survey

The goal of the survey of the ATLAS pixel endcap modules is to provide the position and orientation of the 48 pixel modules on each of the 6 disks, including any misalignments due to the placement of the modules on the sector and the placement of the sectors on the disk ring. These survey module alignment parameters are put into the conditions database, and are then used in the track reconstruction. The absolute positions of the disks or of the pixel endcap are not measured in this survey.

2.3.2 Module Alignment Parameters

The pixel endcap module is treated as flat rigid plane, as the module distortions (such as bow) are very small. The bow of the module is defined as the distance of the module center to the plane defined by the module ends. Figure 4 shows the distribution of the bow measurements for all modules. The Gaussian fit to the bow distribution has a mean of 3 microns and a sigma of 8 microns. This small amount of bow has a negligible effect on the spatial resolution. Tobias Golling (LBNL) studied the effects of 60 micron module distortions on the five track parameter resolutions, and found a negligible effect (1% or less).

The local module coordinate system is shown in Figure 5 for "12:00 o'clock" modules in Endcap A and Endcap C, as seen from the interaction point (IP). Thus for modules on A disks:

- for a "12:00 o'clock" module X is to the right and Y is up (as seen from the IP),
- for a "6:00 o'clock" module X is to the left and Y is down (as seen from the IP).

For modules on C disks:

- for a "12:00 o'clock" module X is to the left and Y is up (as seen from the IP),
- for a "6:00 o'clock" module X is to the right and Y is down (as seen from the IP).

For all modules, Y is always in the outward radial direction. X,Y,Z form the usual right-handed coordinate system.

The module alignment parameters in the local module reference frame are those 6 parameters used to describe a flat plane:

$$X, Y, Z, \Phi_X, \Phi_Y, \Phi_Z$$

where:

- X,Y is the position of the module center [mm].
- Z is the midpoint of the silicon sensor at the module center [mm].
- Φ_X is the rotation of the module about the X (short) axis [mrad].
- Φ_Y is the rotation of the module about the Y (long) axis [mrad].
- Φ_Z is the rotation of the module about the Z axis [mrad].

The 3 phi angles are simple rotations, not Euler angles. Their order of application does not matter, since all the angles are so small.

In the local module reference frame, the nominal module positions are $X=Y=Z=\Phi_X=\Phi_Y=\Phi_Z=0$. Thus the module alignment parameters are the displacements of the module from its nominal position (i.e. the difference from nominal).




Figure 4: Distribution of the module bow, for all pixel endcap modules.

EC A Module

EC C Module




Figure 5: Local module coordinate system for “12:00 o’clock” modules in Endcap A and in Endcap C, as seen from the interaction point.

2.3.3 Description of the Sector and Disk Surveys

Figure 6 shows three endcap modules mounted on a sector. For the surveys, the sector (or disk) is mounted on the table of an optical SmartScope. The SmartScope very precisely measures X,Y coordinates (in the plane of the sector) by measuring the position of the table, and measures Z coordinates (perpendicular to the sector) with optical focusing.

When the pixel endcaps are installed in Atlas, the so-called "front" modules are on the sides of the sectors facing towards the interaction point, and the so-called "back" modules are on the sides of the sectors facing away from the interaction point.

To determine the module alignment parameters three different types of surveys of modules were done:

- X,Y sector survey:** Measured the X,Y position of survey targets at the 4 corners of front and back modules mounted on a sector. Survey is done before mounting sectors on disks.
- Z sector survey:** Measured 32 X,Y,Z points on the top side of all modules (16 along one long edge, 16 along the other long edge) in the vicinity of the first and last chip ID pads of each front-end chip. The Z values are with respect to the plane of the sector (determined by the surfaces of the 3 mounting buttons). Survey is done before mounting sectors on disks.
- X,Y disk survey:** Measured the X,Y position of survey targets at the 4 corners of front modules on sectors mounted on disks.

The data from each of the above surveys were used in the following ways:

- X,Y sector survey:** Used to calculate the X, Y, Φ_z of front and back modules on a sector, due to the placement of the module on the sector. These are not the final X, Y, Φ_z survey alignment parameters, as they do not include the effect of the placement of the sector on the disk ring.
- Z sector survey:** Used to calculate the Z, Φ_x, Φ_y of front and back modules on a sector, due to the placement of the module on the sector. These are the final Z, Φ_x, Φ_y survey alignment parameters since no Z information was obtained during the disk surveys.
- X,Y disk survey:** Used to directly calculate the final X, Y, Φ_z of front modules, due to the placement of the module on the sector and the placement of the sector on the disk ring.
- Used to indirectly calculate the final X, Y, Φ_z of back modules:
- It is assumed there is a small translation and rotation of a sector from nominal when it is mounted on the disk ring, which is determined from a fit to the differences in the local module positions of the three front modules between the X,Y sector survey and the X,Y disk survey. It is found that these fits of the sector movement are good to a couple of microns, which validates the above assumption.
 - Use this calculated sector movement to calculate how much the back modules move from nominal when the sectors are placed on the disk ring.
 - Add this calculated movement of the back modules to the X, Y, Φ_z of back modules from the X,Y sector survey results, to get the final X, Y, Φ_z parameters of back modules for both effects (the placement of the modules on the sector and the placement of the sectors on the disk ring).

2.3.4 Calculation of the Survey Module Alignment Parameters

The six survey module alignment parameters were calculated from the survey data with the following procedure:

Using the **X,Y sector/disk survey data**, calculated:

- X,Y:** The X and Y of the module center, in the sector reference frame, are calculated as the average of the 4 target X values and the 4 target Y values, respectively. They are then transformed to the local module reference frame.
- Φ_z :** This angle is also determined from the X,Y positions of the 4 targets at the corners of each module. The angle of rotation is calculated for each target, using the X,Y of the target and the X,Y of the module center. The average of the 4 angles is calculated for each module. Φ_z is the difference between this average value of rotation and the nominal value of rotation, for each module.

Using the **Z sector survey data**, calculated:

- Z:** The 32 X,Y,Z points measured along the module edges were fit to a flat 3D plane using a ROOT macro, giving a module plane. The equation of the module plane was then transformed from the sector coordinate system to the local module coordinate system, resulting in $Z = d + e*X + f*Y$. Z has been corrected here to be that of the midpoint of the silicon, with respect to nominal. Thus Z at the module center = d .
- Φ_x, Φ_y :** Since these angles are small, from the above equation: $\Phi_x = f$, $\Phi_y = -e$ (using the normal right hand definition of angles).




Figure 6: Three endcap pixel modules mounted on a sector.

3 Storage of Survey Data

Survey data need to be stored in several places.

In this section are described:

- the directory structure in the RawDatabaseServer where barrel raw data are to be stored
- definition of PDB tests that will contain:
 - summary data for stave survey
 - summary data from halfshell survey
- data from the sector and disk surveys.

In the following tables, the precision indicates the number of decimal digits. This is typically equivalent to a rounding error of 0.1 μm or 0.001°, which should match the printout format of most CMMs.

3.1 RDB Data Structure

The typical directory structure on the Raw Database Server is:

Component Type/Serial Number/Test Type/Test version number

Files containing stave survey data are therefore in:

StaveAssembly/2021200###4###/SURVEY/##/

and

StaveAssembly/2021200###4###/SUMMARY/##/

where # indicates a digit.

Halfshell survey raw data will be in:

L2_HalfShAssemblyBot/20212001120121/SURVEY/##

L2_HalfShAssemblyTop/20212001120122/SURVEY/##

L1_HalfShAssemblyBot/20212001120111/SURVEY/##

L1_HalfShAssemblyTop/20212001120112/SURVEY/##

BL_HalfShAssemblyBot/20212001120101/SURVEY/##

BL_HalfShAssemblyTop/20212001120102/SURVEY/##

3.2 PDB Test Definition

3.2.1 Sphere Coordinates

This test was originally defined for both Stave and StaveAssembly objects.

Data collected in the Stave survey need to be updated and attached to the relevant StaveAssembly item.

Test name is **Stave Coord**.

The data content is shown in Table 3.

Table 3: Structure of the Stave Coord test.

Name	type	units	range / precision	Description
X1	float	mm	4-8 / 0.0001 mm	X coordinates of sphere C in the stave reference system
Y1	float	mm	0-4 / 0.0001 mm	Y coordinates of sphere C in the stave reference system
Z1	float	mm	400-450 / 0.0001 mm	Z coordinates of sphere C in the stave reference system
X2	float	mm	4-8 / 0.0001 mm	X coordinates of sphere A in the stave reference system
Y2	float	mm	0-4 / 0.0001 mm	Y coordinates of sphere A in the stave reference system
Z2	float	mm	-400 - -450 / 0.0001 mm	Z coordinates of sphere A in the stave reference system

3.2.2 Stave survey

The test is attached to StaveAssembly objects.

Test name is **STSurvey**.

Test content is defined in Table 4.

Table 4: Structure of the STSurvey test

Name	type	units	range / precision	Description
M6C_X	float	mm	-2 – 2 / 0.0001 mm	X coordinate of center of module M6C in the stave reference system
M6C_Y	float	mm	-4 – 4 / 0.0001 mm	Y coordinate of center of module M6C in the stave reference system
M6C_Z	float	mm	-400 – 400 / 0.0001 mm	Z coordinate of center of module M6C in the stave reference system
M6C_EX	float	degrees	-3 – 3 / 0.001°	Rotation about the an axis parallel to the stave X axis and passing about the module center.
M6C_EY	float	degrees	-2 – 2 / 0.001°	Rotation about the an axis parallel to the stave Y axis and passing about the module center.
M6C_EZ	float	degrees	-2 – 2 / 0.001°	Rotation about the an axis parallel to the stave Z axis and passing about the module center.
M6C_1RP	float	mm ⁻¹	-0.002 – 0.002 / 10 ⁻⁶	Inverse of curvature radius measured at ~x=11 mm. That range should correspond to ±1 mm bow with a precision of 0.5 μm
M6C_1RN	float	mm ⁻¹	-0.002 – 0.002 / 10 ⁻⁶	Inverse of curvature radius measured at ~x=-11 mm. That range should correspond to ±1 mm bow with a precision of 0.5 μm
M6C_TW	float	degrees	-1 – 1 / 0.001°	Difference between EX measurement at x=±11 mm

... same 9 words repeated for modules M5C-M1C, M0, M1A-M6A

In the following, the module parameters in the table above will be referred dropping the prefix “M#_”.

In the ATLAS convention local X on a module is along the precise measurement, local Y is along the lower precision measurement (in the direction of the ATLAS Z), local Z is perpendicular to the module and going toward the outer radius (so ingoing to the module).

This does not agree with the convention for stave survey (for staves local Y is the stave Z and local Z is similar to stave Y).

Moreover the survey points in the direction perpendicular to the stave plane are taken at the surface of the front-end chips which is lower by about $125 \mu\text{m}$ (half the sensor thickness) + $5 \mu\text{m}$ (approximate bump height) with respect to the center of the sensitive region.

Finally to take into account module bowing, a further shift is applied to set the average module z correction to zero.

To take into account these different conventions, the following transformation is used to move from the local module frame to a frame more similar to the stave frame:

$$A_0 = \left(\begin{array}{ccc|c} 1 & 0 & 0 & 0 \\ 0 & 0 & 1 & d \\ 0 & -1 & 0 & 0 \end{array} \right)$$

where the first part is the rotation matrix (applied after the translation) and the second part is the translation.

The vertical correction d is given by:
$$d = 130 \mu\text{m} + \frac{1}{24} \frac{1 + \tan^2 \frac{\theta}{2} + \tan^4 \frac{\theta}{2}}{\sqrt{1 + \tan^2 \frac{\theta}{2}}} L^2 \frac{k_+ + k_-}{2}$$

where θ is the twist angle TW from the survey, L is the size of the active area, 60.8 mm, and k_{\pm} are the curvature parameters 1RP and 1RN respectively. This offset is chosen such that the average vertical correction to the average plane is zero.

The full transformation in the stave frame is obtained by applying A_0 , followed by an affine transformation, derived by parameters X, Y, Z and EX, EY, EZ:

$$A_1 = \left(\begin{array}{ccc|c} R_x & R_y & R_z & X \\ & & & Y \\ & & & Z \end{array} \right)$$

Where the rotation matrixes R_i are given by (slight inconsistencies in the sign are due to the way the data are stored in the survey):

$$R_x = \left(\begin{array}{ccc} 1 & 0 & 0 \\ 0 & \cos EX & \sin EX \\ 0 & -\sin EX & \cos EX \end{array} \right)$$

$$R_y = \left(\begin{array}{ccc} \cos EY & 0 & \sin EY \\ 0 & 1 & 0 \\ -\sin EY & 0 & \cos EY \end{array} \right)$$

$$R_z = \left(\begin{array}{ccc} \cos EZ & -\sin EZ & 0 \\ \sin EZ & \cos EZ & 0 \\ 0 & 0 & 1 \end{array} \right)$$

Finally, the complete transformation from the local module frame to the stave frame is given by the composition of A_0 and A_1 : $A(\text{local} \rightarrow \text{stave}) = A_1 A_0$

3.2.3 Halfshell survey

The test is attached to StaveAssembly objects.

Test name is **HSSurvey**.

Test content is defined in Table 5.

Table 5: Structure of HSSurvey test.

Name	type	units	range / precision	Description
SPHA_X	float	mm	-200 – 200 / 0.0001 mm	X coordinates of sphere A in the ATLAS reference system
SPHA_Y	float	mm	-200 – 200 / 0.0001 mm	Y coordinates of sphere A in the ATLAS reference system
SPHA_Z	float	mm	400-450 / 0.0001 mm	Z coordinates of sphere A in the ATLAS reference system
SPHC_X	float	mm	-200 – 200 / 0.0001 mm	X coordinates of sphere C in the ATLAS reference system
SPHC_Y	float	mm	-200 – 200 / 0.0001 mm	Y coordinates of sphere C in the ATLAS reference system
SPHC_Z	float	mm	-400 - -450 / 0.0001 mm	Z coordinates of sphere C in the ATLAS reference system
PLA_NX	float	degrees	0 – 180 / 0.001°	Angle between the unit vector perpendicular to plane below A side sphere and the X axis of the ATLAS reference system
PLA_NY	float	degrees	0 – 180 / 0.001°	Angle between the unit vector perpendicular to plane below A side sphere and the Y axis of the ATLAS reference system
PLA_NZ	float	degrees	0 – 180 / 0.001°	Angle between the unit vector perpendicular to plane below A side sphere and the Z axis of the ATLAS reference system
PLA_D	float	mm	-500 – 500 / 0.0001 mm	Constant term of equation of plane below A side sphere in the ATLAS reference system
PLC_NX	float	degrees	0 – 180 / 0.001°	Angle between the unit vector perpendicular to plane below C side sphere and X axis in the ATLAS reference system.
PLC_NY	float	degrees	0 – 180 / 0.001°	Angle between the unit vector perpendicular to plane below C side sphere and Y axis in the ATLAS reference system
PLC_NZ	float	degrees	0 – 180 / 0.001°	Angle between the unit vector perpendicular to plane below C side sphere and Z axis in the ATLAS reference system
PLC_D	float	mm	-500 – 500 / 0.0001 mm	Constant term of equation of plane below C side sphere in the ATLAS reference system.
PL_NX	float	degrees	0 – 180 / 0.001°	Angle between the unit vector perpendicular to stave plane and the X axis in the ATLAS reference system
PL_NY	float	degrees	0 – 180 / 0.001°	Angle between the unit vector perpendicular to stave plane and the Y axis in the ATLAS reference system
PL_NZ	float	degrees	0 – 180 / 0.001°	Angle between the unit vector perpendicular to stave plane and the Z axis in the ATLAS reference system
PL_D	float	mm	-500 – 500 / 0.0001 mm	Constant term of equation of stave plane in the ATLAS reference system.

The vector normal to the average stave plane has components given by:

$$\mathbf{n} = (\cos(\text{PL_NX}), \cos(\text{PL_NY}), \cos(\text{PL_NZ}))$$

and so on for the other planes.

The orientation of \mathbf{n} is defined to be toward the center of ATLAS.

The value of PL_D is such that the plane is defined by equation

$$\mathbf{n} \cdot \mathbf{x} + \text{PL_D} = 0$$

Since the value of \mathbf{x} for which the above equation will be used range up to ~1000 mm, the cosines must be computed with a precision of order of 10^{-7} , and `double` numbers are required.

The transformation from the stave survey frame to the ATLAS frame is computed using the projections of the center of spheres onto the average stave plane. It is found by matching the following items in the two frames:

- the mid-point of the two spheres' projections;
- the unit vector $\mathbf{n} = (\cos(\text{PL_NX}), \cos(\text{PL_NY}), \cos(\text{PL_NZ}))$ with the normal to the $y=0$ plane in the stave survey $\mathbf{j}=(0,1,0)$;
- the unit vector along the direction joining the two spheres' projections.

3.3 Data from Sector and Disk Surveys

A 5 MB zipped folder, EC_Pixel_Survey_Data.zip, contains:

Folders, which contain files with the original survey measurements. The survey measurements are entered into the Excel files by the execution of Excel macros, which read many files from the folders.

Excel files, which contain both the raw data values (the X,Y,Z measurements of targets and points on the modules from the sector and disk surveys) and the necessary step-by-step calculations that must be done to produce module positions from the raw data values.

Text files, which contain the final survey module alignment parameters for the conditions data base.

The **folders** are:

disk_surveys:	Raw data from X,Y disk surveys.
module_Z_survey:	Raw data from Z sector surveys.
sector_module_results:	Processed raw data from Z sector surveys.
sector_survey_summaries:	Raw data from X,Y sector surveys.

The **Excel files** for the analysis of the data from the **X,Y sector surveys** and **Z sector surveys** are:

Module_Tilt_Angles.xls:	Translate and rotate module plane equations to local module frame.
XYZ_Sector>Loading_Stats.xls:	Summary of bow, tilt, XY placement, etc measurements.
Z_Survey_Measuremts.xls:	Process raw Z measurements from Z sector surveys.
Module_positions_on_sectors.xls:	Calculation of alignment parameters for modules from sector surveys.
Disk_0A_V1.xls:	Module alignment parameters from sector surveys.
Disk_1A_V1.xls:	Module alignment parameters from sector surveys.
Disk_2A_V1.xls:	Module alignment parameters from sector surveys.
Disk_0C_V1.xls:	Module alignment parameters from sector surveys.
Disk_1C_V1.xls:	Module alignment parameters from sector surveys.
Disk_2C_V1.xls:	Module alignment parameters from sector surveys.

The **Excel files** for the calculation of the survey module alignment parameters from the **X,Y disk surveys** are:

Disk_0A_V2.xls
Disk_1A_V2.xls
Disk_2A_V2.xls
Disk_0C_V2.xls
Disk_1C_V2.xls
Disk_2C_V2.xls

The **Text files** with the **final survey module alignment parameters** for the conditions data base are:

Survey_Align_Param_Pixel_Disk_0A_V3.txt
Survey_Align_Param_Pixel_Disk_1A_V3.txt
Survey_Align_Param_Pixel_Disk_2A_V3.txt
Survey_Align_Param_Pixel_Disk_0C_V3.txt
Survey_Align_Param_Pixel_Disk_1C_V3.txt
Survey_Align_Param_Pixel_Disk_2C_V3.txt

4 Summary of results

4.1 Results for Barrel Modules

4.1.1 Comparison between stave and halfshell survey

Reconstruction of the barrel geometry requires overlapping the measurements coming from stave and halfshell survey, using the ruby balls.

Consistency checks on these measurements have been performed. Figure 7 shows the distance between the ruby balls as measured in the stave survey and in the halfshells survey. The agreement is good, with an r.m.s. of 19 μm and no evidence of a systematic difference (average over 112 staves is -3 μm).




Figure 7: Comparison of the ruby balls distance between the halfshell and stave surveys. The residuals have a r.m.s. of 19 μm .




Figure 8: Height of the ruby balls over the stave plane. The two populations correspond to different batches of stave production (Polyform and IVW). The r.m.s. of the difference is 26 μm .

Figure 8 compares the height of the spheres over the average plane. There is a good correlation between the two measurements, with a pair of outliers probably due to a swapping of the stave survey data for stave 4027. The two populations are due to two different batches of stave production: the original Polyform ones cluster at 1.5 mm height, while the more recent IVW staves cluster around 1 mm height.

In this case the r.m.s. of the differences is 26 μm .

Overall we can therefore quote a systematic error due to the stave/halfshell survey mismatch of about 20 μm .

4.1.2 Module distortions

A summary of the distortion parameters k_{\pm} and θ , mentioned in section 2.1.4, is reported in Figure 9. The distortion size is provided in the caption.

As to the module curvature, while there is good correlation between the curvature on the two sides, an asymmetrical distribution is observed, with the curvature on the negative x side weaker than the one on the positive side. Also the twist parameter θ has an asymmetric distribution.

This effect has been traced to be due to the pick-up tool used for stave loading in Genova, which was slightly distorting the modules during the loading.




Figure 9: Distortion parameters: on the left side, comparison between the curvature on the two sides of the modules. In this scale 0.1 m^{-1} corresponds to a sagitta over the module length of 45 μm . Right side is the θ parameter distribution. The 0.05° r.m.s. is equivalent to a $\pm 25 \mu\text{m}$ height difference on the edges.




Figure 10: Deviation from nominal position of module centers according to the stave survey.

4.1.3 Comparison to ideal halfshell geometry

Within one stave, the module deposition procedure is quite precise, giving a relatively small deviation from the nominal position, as shown in Figure 10, where the in-plane coordinates have an r.m.s. of 30 μm , while the r.m.s. is wider for the vertical coordinate.

Note that the y position is not corrected for the glue and sensor thickness.

The bigger effect instead is the placement of the stave into the halfshell, which has lesser constraints and is mainly a manual operation, different from the module deposition which is largely computer controlled.

In this case, the radial position instead is better fixed by the mechanics (Figure 11).

Placement tolerances of the order of a couple of hundred micrometers can instead be expected in the $R\Phi$ and z coordinates (Figure 12).

The convolution of these two effects results in the statement that barrel modules will be displaced from the nominal position by order of 200 μm . Since the survey accuracy is much better than that (see Section 2.2.2), it is expected the usage of the survey data will definitely improve the starting point for the alignment.




Figure 11: Radial position of stave after placing on the halfshell.




Figure 12: Deviation from nominal of the center of stave position, in the $R\Phi$ and Z coordinates.

4.2 Results for Disk Modules

4.2.1 Results of the X,Y and Z sector surveys

Using the data from the X,Y sector surveys and the Z sector surveys described in Section 2.3.3, the six module alignment parameters (X , Y , Z , Φ_X , Φ_Y , Φ_Z) were calculated (in the local module reference frame) for all front and back modules, as described in Section 2.3.4. These alignment parameters are the displacements from nominal due only to the placement of the module on the sector. The X,Y,Φ_Z alignment parameters calculated here from the X,Y sector surveys are not the final survey alignment parameters, as they do not include the effect of the placement of the sector on the disk ring. The Z,Φ_X,Φ_Y alignment parameters calculated here from the Z sector surveys are the final survey alignment parameters, since no good Z information was obtained during the disk surveys.

In Figure 13 are the distributions of the X,Y,Φ_Z module alignment parameters calculated from the X,Y sector surveys (treating all the modules as A Disk modules, which means plotting the negative of the actual X and Φ_Z values for the C Disk modules), and in Table 6 are the means and sigmas of the Gaussian fits to these distributions. One sees several features:

- The mean of the X alignment parameter distribution is different for front and back modules: -2.8 microns for front modules, and $+2.8$ microns for back modules. This is due to a small systematic offset when the modules were mounted on the sectors. The opposite sign occurs when converting the survey measurements to the same coordinate system.
- The average sigma for the X and Y alignment parameter distributions is 2.0 microns, and the sigma for the Φ_Z alignment parameter distribution is 0.064 mrad. These resolutions include both the placement accuracy and the measurement precision, and thus represent upper limits on the placement accuracy. These small values show that the modules have been placed on the sectors with excellent accuracy. The measurement precision of the alignment parameters is in Section 4..3.




Figure 13: X,Y,Φ_Z alignment parameters calculated from the X,Y sector surveys

	Mean	Sigma
X for Front Modules	$-2.8 \pm 0.2 \mu$	$2.1 \pm 0.2 \mu$
X for Back Modules	$2.8 \pm 0.1 \mu$	$1.4 \pm 0.1 \mu$
Y for Front and Back Modules	$-0.1 \pm 0.1 \mu$	$2.3 \pm 0.1 \mu$
Φ_Z for Front and Back Modules	$-0.011 \pm 0.004 \text{ mrad}$	$0.064 \pm 0.004 \text{ mrad}$

Table 6: Means and sigmas of the Gaussian fits to the sector survey distributions in Figure 13.

In Figure 14 are the distributions of the final Z, Φ_X, Φ_Y module alignment parameters calculated from the Z sector surveys (treating all the modules as A Disk modules, which means plotting the negative of the actual Z and Φ_X values for the C Disk modules), and in Table 7 are the means and sigmas of the Gaussian fits to these distributions. The mean of the Z alignment parameter distribution is different for front and back modules: +50 microns for front modules, and -14 microns for back modules. In the calculation of these Z alignment parameters it was assumed that the nominal Z value of the midpoint of the silicon sensor was ± 2.1 mm from the midpoint of the sector. Thus while the nominal distance between the midpoints of the silicon of front and back modules is 4.2 mm, the Z sector survey shows that it is actually 4.264 mm, averaged over all modules.




Figure 14: Final Z, Φ_X, Φ_Y alignment parameters calculated from the Z sector surveys.

	Mean	Sigma
Z for Front Modules	$50.4 \pm 1.9 \mu\text{m}$	$21.7 \pm 1.7 \mu\text{m}$
Z for Back Modules	$-14.2 \pm 2.4 \mu\text{m}$	$26.6 \pm 1.9 \mu\text{m}$
Φ_X for Front and Back Modules	$-0.339 \pm 0.033 \text{ mrad}$	$0.545 \pm 0.026 \text{ mrad}$
Φ_Y for Front and Back Modules	$0.029 \pm 0.030 \text{ mrad}$	$0.482 \pm 0.024 \text{ mrad}$

Table 7: Means and sigmas of the Gaussian fits to the sector survey distributions in Figure 14.

4.2.2 Results of the X,Y disk surveys

Using the data from the X,Y disk surveys described in Section 2.3.3, the final X,Y, Φ_z alignment parameters of front modules were directly calculated and the final X,Y, Φ_z alignment parameters of back modules were indirectly calculated, as described in Sections 2.3.3 and 2.3.4. All alignment parameters are in the local module reference frame. These final X,Y, Φ_z alignment parameters calculated here are the displacements from nominal due to both the placement of the modules on the sector and the placement of the sectors on the disk ring.

In Figure 15 are the distributions of the final X,Y, Φ_z alignment parameters calculated from the X,Y disk surveys (treating all the modules as A Disk modules, which means plotting the negative of the actual X and Φ_z values for the C Disk modules), and in Table 8 are the means and sigmas of the Gaussian fits to these distributions. One sees several features:

- The average sigma for the X and Y alignment parameter distributions is 12 microns, and the sigma for the Φ_z alignment parameter distribution is 0.130 mrad. These values include both the placement of the modules on the sector and the placement of the sectors on the disk ring. Recall from the X,Y sector survey results (which only include the placement of the modules on the sector), that the average sigma for X and Y was 2.0 microns, and the sigma for Φ_z was 0.064 mrad. Thus we see a much larger variation in the module position due to the sectors being placed on the disk ring than due to the modules being placed on the sector.
- The mean of the Y alignment parameter distribution is 35 microns. The local module Y direction is the radial direction in the disk. The reason that the Y alignment parameter is so large is mostly because the average radius of the mounting holes in the disk rings is larger than the nominal value of 156 mm. From independent disk ring measurements, the radius appears to be roughly 25 microns larger than nominal. This accounts for the major part of the 35 microns.




Figure 15: Final X,Y, Φ_z alignment parameters calculated from the X,Y disk surveys.

	Mean	Sigma
X for Front Modules	$-0.1 \pm 1.1 \mu$	$12.6 \pm 0.9 \mu$
X for Back Modules	$1.1 \pm 1.0 \mu$	$11.5 \pm 0.8 \mu$
Y for Front and Back Modules	$35.3 \pm 0.7 \mu$	$11.4 \pm 0.6 \mu$
Φ_z for Front and Back Modules	$-0.029 \pm 0.008 \text{ mrad}$	$0.130 \pm 0.009 \text{ mrad}$

Table 8: Means and sigmas of the Gaussian fits to the disk survey distributions in Figure 15.

4.2.3 Measurement Precision and Stability

The measurement precision is determined by comparing the X,Y module alignment parameters calculated from two X,Y disk surveys taken one right after the other. This was done for two disks, Disk 0A and Disk 1A. In Figure 16 are the distributions of the difference in the X module alignment parameters, and the difference in the Y module alignment parameters, for two surveys of these disks taken one right after the other. In Table 9 are the means and sigmas of the Gaussian fits to these distributions. Dividing the average sigma of these difference distributions by $\sqrt{2}$ gives about 0.4 microns for the statistical precision of measuring the X,Y module alignment parameters.




Figure 16: For two X,Y disk surveys taken one right after the other: a) Difference in the X module alignment parameters, b) Difference in the Y module alignment parameters.

	Mean	Sigma
Difference in the X alignment parameters	$0.05 \pm 0.05 \mu$	$0.48 \pm 0.05 \mu$
Difference in the Y alignment parameters	$-0.32 \pm 0.06 \mu$	$0.59 \pm 0.06 \mu$

Table 9: Means and sigmas of the Gaussian fits to the difference distributions in Figure 16.

The stability during a month of handling of a disk is determined by comparing the X,Y module alignment parameters calculated from two X,Y disk surveys taken one month apart. This was done for Disk 2A. During the month of handling Disk 2A was moved from one building to another and back by car (~2 miles round trip), U-tubes and exhaust tubes were added, the disk was transferred from the disk holder to the sector loading tool, 2 sectors were removed, and 2 sectors were loaded on the disk. This stability study only used the six sectors that were not removed. For the three “front” modules in each of those six sectors, Figure 17 shows the distributions of the difference in the X module alignment parameters, and the difference in the Y module alignment parameters, for two surveys of Disk 2A taken one month apart. In Table 10 are the averages and RMS of these distributions. It is seen that the stability of the measurements of the X,Y module alignment parameters is about 1 micron over a month of handling.




Figure 17: For two X,Y disk surveys taken one month apart: a) Difference in the X module alignment parameters, b) Difference in the Y module alignment parameters.

	Average	RMS
Difference in the X alignment parameters	0.0 μ	0.9 μ
Difference in the Y alignment parameters	-0.7 μ	1.0 μ

Table 10: Averages and RMS of the difference distributions in Figure 17.

4.2.4 Additional Uncertainty for Back Module Alignment Parameters

As seen from the previous Sections, the final X,Y, Φ_z survey alignment parameters for the front modules of a sector were determined from SmartScope measurements done after the sectors were attached to the disk rings (the "X,Y disk survey"). But the back modules were not measured after the sectors were attached to the disk rings; their positions were only measured when they were mounted on the sectors. Thus to get the analogous final X,Y, Φ_z survey alignment parameters for the back modules requires an additional step (using the positions of the back modules relative to the front modules from the measurements of the front and back modules on the individual sectors in the "X,Y sector survey"). This introduces several additional sources of uncertainty for the alignment parameters of the back modules, which are listed in Table 11. When added in quadrature, they equal about 5 microns.

RMS Error (microns)	Source
<1	Basic statistical precision of measuring the module center
1	Stability of precision after a month of handling of a disk
4	Back module position relative to front modules in the sector survey
2	Movement of modules between surveying them on sectors and surveying them on disks
2	Extrapolation of back module measurements on sectors to back module positions on disks
5	TOTAL (added in quadrature)

Table 11: Additional sources of uncertainty for the alignment parameters of the back modules.

The 4 micron uncertainty due to the "Back module position relative to front modules in the sector survey" is due to the error in measuring the reference holes on the front and back sides of the sector, and the variation of the actual distance between the holes. It was determined by using the measured positions of the two reference holes to calculate the distance between them, and then calculating the variation of that distance from nominal.

The 2 micron uncertainty due to the "Movement of modules between surveying them on sectors and surveying them on disks" was determined by comparing the distance between targets on neighboring modules from the sector survey measurements to the same quantity from the disk survey measurements, for the front modules. It is assumed that the results apply equally well to the back modules. For front modules this movement is accounted for since the front modules are measured again after mounting the sectors on the disks, but this is not true for the back modules.

Finally, there is a 2 micron uncertainty due to the "Extrapolation of back module measurements on sectors to back module positions on disks". It is assumed there is a small translation and rotation of a sector from nominal when it is mounted on the disk ring, which is determined from a fit to the differences in the local module positions of the three front modules between the X,Y sector survey and the X,Y disk survey. The sector fits are used along with the positions of the back modules from the X,Y sector surveys to calculate the final X,Y, Φ_Z survey alignment parameters for the back modules. The 2 micron uncertainty arises from the uncertainty in the fits.

4.2.5 Conclusion for Disk Modules

The X, Y, Z, Φ_X , Φ_Y , Φ_Z survey alignment parameters of the 48 pixel modules on each of the 6 endcap disks have been determined. These alignment parameters give the position and orientation of each module due to the effects of the placement of the modules on the sector and the placement of the sectors on the disk ring. The distributions of the final survey module alignment parameters are in Figures 14 and 15, and the means and sigmas of the Gaussian fits to these distributions are in Tables 7 and 8. The statistical uncertainty in the X,Y survey module alignment parameters is about 1 micron for front modules, and about 5 microns for back modules.

References

- [1] *Procedure for building the Loading Reference System on the New Stave* ATL-IP-FP-0025
- [2] *Pixel Sensor Parameters* ATL-IP-EP-0011
- [3] *Fiducial balls purchasing specifications* ATL-IP-ES-0043
- [4] *Engineering drawing of the new TMT halves* ATL-IP-ED-0201
- [5] *Barrel Layout Parameters* ATL-IP-EP-0015